

## Flat Decks – Hook Lift or Cable Systems

Available in 14ft – 24ft lengths and 54" or 62" hook heights

### Frame Assembly:

- Hook Lift Main rails 6" x 2" x 1/4" steel tube
- Cable Pull Main rails 6" x 2" x 3/16" steel tube
- Outside rails 5" x 2" x 3/16" steel tube
- Cross members 3" x 3" x 1/8" steel tube on 18" centers
- External stake pockets 24" on center
- Rub rail 1/2" x 3" flat bar
- 3/4" D rings at each corner
- 5 1/2" diameter wheels
- 2 x 6 T&G fir decking
- Urethane epoxy primer
- Painted black with urethane epoxy
- Reflective tape on front, sides & rear



### Headache Rack:

- Frame 4 x 2 x 3/16" steel tube
- Lower half 1/8" steel checker plate
- Upper half 3/49R expanded metal
- 3/4" diameter round bar handles on front of both uprights

### Options:

- Side mounted low profile load strap winches
- 16" fixed mounted beavertail

### Warranty

Each product manufactured by SCS Steel Container Systems Inc. is backed by warranty to be free from defect in material and workmanship. For our complete warranty statement, see our web site or contact us.

*Strong and Structured Systems, Strong and Structured Products.*

[www.scsinc.ca](http://www.scsinc.ca)